

Tabela robót ziemnych ul. Krótka

PIKIETAŻ	POWIERZCHNIA		OBJĘTOŚĆ		ZUŻYCIE		BILANS
	WYKOP	NASYP	WYKOP	NASYP	NA MIEJSCU	NADMIAR	
0.00	9.47	0.00					0.00
			44.98	0.48	0.48	44.51	
7.32	2.82	0.13				44.51	44.51
			63.96	6.35	6.35	57.61	
30.00	2.82	0.43				102.11	102.11
			65.70	6.80	6.80	58.90	
50.00	3.75	0.25				161.01	161.01
			78.75	4.78	4.78	73.97	
68.75	4.65	0.26				234.98	234.98
68.75	4.66	0.25				234.98	234.98
			51.64	2.14	2.14	49.50	
80.00	4.52	0.13				284.48	284.48
			13.51	0.35	0.35	13.16	
83.05	4.34	0.10				297.64	297.64
83.05	4.25	0.00				297.64	297.64
			42.39	0.00	0.00	42.39	
92.47	4.75	0.00				340.03	340.03
			35.88	0.00	0.00	35.88	
100.00	4.78	0.00				375.91	375.91
			5.98	0.00	0.00	5.98	
101.25	4.79	0.00				381.89	381.89
101.25	5.05	0.06				381.89	381.89
			81.43	0.47	0.47	80.95	
117.00	5.29	0.00				462.85	462.85
			36.54	0.00	0.00	36.54	
124.00	5.15	0.00				499.39	499.39
			25.40	0.10	0.10	25.30	
129.00	5.01	0.04				524.69	524.69
			39.52	1.21	1.21	38.32	
138.30	3.49	0.22				563.00	563.00
			33.46	3.63	3.63	29.84	
150.00	2.23	0.40				592.84	592.84
			11.97	2.85	2.85	9.12	
155.70	1.97	0.60				601.96	601.96
			4.05	0.68	0.68	3.38	
157.55	2.41	0.13				605.34	605.34
			12.54	0.20	0.20	12.34	
160.62	5.76	0.00				617.68	617.68
			14.14	0.00	0.00	14.14	
162.74	7.58	0.00				631.82	631.82
RAZEM			661.85	30.03	30.03		

PROJEKTANT

inż. Waldemar Henryk Adamiec
 Nr upr. projekt. i bud. I AN-4224-46.5545